INTRODUCTION

Post-Installation meetings are held to help ensure that General Electric equipment is operating properly, that the Punch List items are promptly acted upon, and that the Customer is satisfied.

This article will discuss the two Post-Installation Meetings that should take place at the completion of every new turbine installation. The two meetings are:

- Internal Post-Installation Meeting
- External Post-Installation Meeting

Internal Post-Installation Meeting

An internal post-installation meeting will be conducted within three (3) months after initial synchronization of the equipment, but no later than the commercial operating date. It is recommended that the persons identified on the following list attend.

- Project Manager (I&FS Order Management)
- Product Service Engineer – Installations
- Product Service Engineer – Maintenance
- I&FS Customer Service Manager*
- I&FS MES
- I&FS Operations Manager*
- I&FS Controls/ Start-up Engineer*
- I&FS Lead TDI Field Engineer*

* Optional

AGENDA

- Punch List Items

  - Shortages

  - Customer Problems

- Identification of Outstanding Work

- Return Surplus Material
- Review Installation Drawings
- Product Dept. Interface Problems
- District Office Interface Problems
- As-Built Marked-Up Drawings
- Final Installation/Start-up Report
- Technical Advisor (TA) Manhours

RECOMMENDED DOCUMENTS

TDI Contract – District.

The objectives in conducting an internal post-installation meeting are as follows.

- Review and identify all GE Punch List items, their completion dates and assigned responsible parties.
- Review, verify, and identify the timeliness and completion of the internal I&FS Punch List items allocating responsibilities and the schedule for completion.
- Identify data for customer post-installation meeting.
- Review problems presented by the customer.
- Review status of all Field Modifications Instructions (FMI) and alteration notices, and obtain assurance that Field Request Notices (FRN) have been opened on all known problems.
- Review equipment shipment, installation, and quality problems.
- Review As-Built installation drawing schedule.
- Review Product Department interface problems.
- Review Final Installation/Start-up Report completion schedule.

- Review Status of TDI Manhours

  - Acceptable/Excessive

  - Chargeable to Customer

EXTERNAL POST-INSTALLATION MEETING

An external post-installation meeting will be conducted in conjunction with, and as soon as possible following, the internal post-installation meeting. It is recommended that the persons identified on the following list attend.

General Electric

- Project Manager (I&FS Order Management)
- Product Service Engineer - Installations
- Product Service Engineer - Maintenance
- I&FS Customer Service Manager*
- I&FS MES
- I&FS Operations Manager*
- I&FS Controls/Start-up Engineer*
- I&FS Lead Field Engineer*

*Optional

Customer

- Project Manager
- Site Manager
- Site Superintendent
- Others (as determined by Customer)

AGENDA

- As-Built Drawings
- Installation and Start-Up Report
- Commercial Operation
- Warranty Administration
- Field Modification Instructions (FMI)
- TDI Manhours (If Applicable)
- Technical Information Letter (TIL)
- Final Punch List

  Note: The Final Punch List (Installation Punch List) is frozen at this meeting. Any new items become Warranty Claims and are handled via the MRN System.

OTHER ISSUES

- Review Equipment Schedule, Installation and Quality Problems
- Customer Evaluation of the Job
- Inspection Intervals

  The first Combustion Inspection should be identified by the Customer at this meeting.

- Review Spare Parts

  A list of Spare Parts should be made available at this meeting.

- Any other issues not specifically identified in this document.

RECOMMENDED DOCUMENTS

TDI Contract – District.

The meeting will be conducted such that all outstanding items are reviewed with the customer. Agreements will be reached and documented concerning the following items.

- Completion of the Punch List Items
- Submittal of the Installation/Start-Up Report
- Completion of the Marked-up "AS-BUILT" Drawings
- Warranty Start Date

After the areas listed above have been addressed, the I&FS obligation will be concluded provided the remaining Punch List items are not associated with the TDI scope of responsibility.

OTHER CONSIDERATIONS

- After the customer meeting, I&FS will publish the finalized Installation Punch List (similar to the form attached at the end of this document), including a schedule and the minutes of the meeting documenting agreements, action items, warranty start date, and commercial operating date.
- The status of the outstanding Punch List items shall be issued monthly by I&FS and distributed to the installation support engineer until all Punch List items are resolved.
- The installation and service engineers will have the option of attending and participating in post-installation meetings.

PUNCH LIST ITEMS

List all Items open at time of report, including Balance of Plant items.

ITEM NO.	DESCRIPTION	PLANNED ACTION	SCHEDULED COMPLETE	RESPONSIBLE PARTY